

**WORK ORDER**  
INDUSTRIAL TECHNOLOGY DEVELOPMENT INSTITUTE

*el 10/11*

Supplier : <b>COLD FRONT TECHNOLOGIES ASIA, INC.</b> Warehouse 7A Las Piñas Commercial Complex, 30 Alabang Zapote Rd. Brgy Address : Talon, Las Piñas City TIN :	P.O. No. : <b>GIAE-PO-2022-04-0256</b> Date : <b>April 12, 2022</b> Mode of Procurement : <b>PB</b>
---	---

Gentlemen:  
Please furnish this Office the following articles subject to the terms and conditions contained herein:

Place of Delivery :	Delivery Term : 90 cd
Date of Delivery :	Payment Term :

Stock/ Property No.	Unit	Description	Quantity	Unit Cost	Amount
1	lot	<b>Fabrication, Supply, delivery and Installation of Indoor Cold storage room in ITDI-PTD Bicutan, Taguig City</b>  PU Panels for Cold Room (6.0m L x 4.0m W x 3.0m H)  Wall & Ceiling:100mm thick polyurethane rigid (PUR) foamed panels, both side 0.426mm thick of PPGI, finish facing - ribs, off white color, polyurethane foam insulation and cold room accessories Floor: double stacked 50mm thick exposed expanded polystyrene (XPS) panels with 0.3mm thick polyethylene (PE) film above and below the stacked XPS, topped with aluminum checkered plate PhP 907753.73	1	3,031,033.35	3,031,033.35
	<i>set</i>	PU Sliding Door 1.5m W x 2.5m H with stainless steel door handle, aluminum sliding channels and PVC strip curtains PhP93152.61	1		
	<i>set</i>	Condensing Unit PhP 362121.42 Bitzer semi-hermetic Piston Compressor, Model: 4CES-9Y Horse Power: 9HP;	1		
	<i>set</i>	Cooling Capacity: 24.7KW; Refrigerant: R404A; Voltage: 220V/60Hz/PH	1		
	<i>set</i>	Variable Frequency Drive <i>2hp</i> PhP89600.00	1		
	<i>set</i>	Evaporator Air Cooler Cooling capacity: 33.6KW; Defrost power: 14.4KW; Danfoss expansion valve; Voltage: 220V/60Hz/3PH,	1		
	<i>set</i>	Humidifier PhP98196.43 Humidifying capacity: 12kg/hour; Applying Space: 180sqm; Water Tank Capacity: 15Liter Diameter of Outlet port: 110mm 2 ports; Power: 1200W; Voltage: 220V/60Hz/3PH	1		
	<i>set</i>	Wired basic controller with Dixell thermostat PhP63771.43	1		
	<i>lot</i>	Materials & Consummables (With civil works) PhP670244.96	1		
	<i>lot</i>	Labor & Commissioning PhP325,228.96	1		
	<i>lot</i>	Mobilization, COVID-19 Safety Requirements, Delivery & Hauling PhP257742.39	1		

**EMAILED**

Date: 04-24-22  
 Time: \_\_\_\_\_

**WORK ORDER**  
INDUSTRIAL TECHNOLOGY DEVELOPMENT INSTITUTE

22 192TF

<b>Supplier :</b> COLD FRONT TECHNOLOGIES ASIA, INC. Warehouse 7A Las Piñas Commercial Complex, 30 Alabang Zapote Rd. Brgy Talon, Las Piñas City <b>Address :</b> <b>TIN :</b>	<b>P.O. No. :</b> GIAE- P10-2022-04-00256 <b>Date :</b> April 12, 2022 <b>Mode of Procurement :</b> PB
---	--


**Gentlemen:**  
Please furnish this Office the following articles subject to the terms and conditions contained herein:


<b>Place of Delivery :</b>	<b>Delivery Term :</b> 90 cd
<b>Date of Delivery :</b>	<b>Payment Term :</b>


Stock/ Property No.	Unit	Description	Quantity	Unit Cost	Amount
		inclusion: - fabrication, assembly and installation of cold room panel - fabrication and installation of equipment platform mounting and installation of equipment (compressor, condenser, evaporator and electrical control panel) - fabrication and installation of support bracket for pipes and electricals - fabrication and installation of ducting piping, electrical, drainage and insulation works - pressure test, leak test, system flushing, vacuuming and refrigerant charging - energize electrical controls fabrication, assembly and installation of VFD system - customized programming of VFD system - start-up, testing and commissioning - 5 days monitoring - concrete topping (min. 100mm thick) and 2 coats (inside + outside) Warranty: Twenty Four (24) months on parts and services			3,031,033.35
<b>END USER:</b>		ERICSON T. MOLASCO	Less: VAT EWT	135,313.99 27,062.80	162,376.71 2,868,656.56

(Total Amount in Words) Two million forty two thousand, one hundred six pesos and 94/100 only

In case of failure to make the full delivery within the time specified above, a penalty of one-tenth (1/10) of one percent for every day of delay shall be imposed on the undelivered item/s.

Conforme:   
**Emilio Gonzalez CA'O**  
 Signature over Printed Name of Supplier  
 5/2/2022  
 Date

Very truly yours,  
  
**ANNABELLE V. BRIONES, PhD**  
 Signature over Printed Name of Authorized Official  
 Director  
 Designation 4/12

<b>Fund Cluster :</b> <u>Grout Fund</u> DOST-GIA: Upgrading the Capability of Existing Distribution Centers/Trading Posts in the Delivery of Fresh and Semi-Processed Agricultural Products in the Supply Chain: Focusing on Packaging Technology and Logistics. <b>Funds Available :</b> ₱ 3,031,033.35  <b>PATRICIA ASILO</b> Accountant II Signature over Printed Name of Chief Accountant/Head of Accounting Division/Unit	<b>ORS/BURS No. :</b> <u>FEU-2022-0631</u> <b>Date of the ORS/BURS:</b> _____ <b>Amount :</b> ₱ 3,031,033.35
--	--

9/04/25